

Cladding Estimate Report

Job: LB-000062
Site:
Date: 11 Sep 2026

Client:
Part: House 1 Cladding

ELEVATIONS

Area	Orientation	Width (m)	Height (m)	Area (m²)	Cladding
North Elevation	Vertical	5.40	2.50	13.50	LTK 51 (Cladding)
Gable	Vertical	2.70	0.60	1.62	LTK 51 (Cladding)

ORDER SUMMARY

Item	Description	Qty	Unit Price	Line Total
Cutlist output	LTK 51 (Cladding)	154.55 lm	\$23.72	\$3665.93

PART TOTAL \$3665.93

LTK 150 BB

Pattern	Stock Length	Qty off	Cuts	Cut Waste	Leftover
Pattern 1	4200mm	1	3	9mm	341mm
Pattern 2	2900mm	5	4	12mm	288mm
Pattern 3	2900mm	42	1	3mm	347mm

Pattern 1 — 4.2m stock, 1 off

ID	Length	Mark	Qty
A	2500 + 50mm	North Elevation	1
B	600 + 50mm	Gable	2
—	341mm	Waste	1

A

B

B

Pattern 2 — 2.9m stock, 5 off

ID	Length	Mark	Qty
A	600 + 50mm	Gable	4
—	288mm	Waste	1

A

A

A

A

Pattern 3 — 2.9m stock, 42 off

ID	Length	Mark	Qty
A	2500 + 50mm	North Elevation	1
—	347mm	Waste	1

A

STICKS	STOCK (LIN. M)	CUT LENGTH	WASTE
48	140.5	124.0m	11.6%