

Estimate Report

Job: LB-000027

Site: My Home

Date: 11 Sep 2026

Client: SP Test Cladding Project

Merchant: Makers Fabrication

ESTIMATE SUMMARY

Unit 1 Cladding (Cladding)	\$2476.72
Unit 1 Midfloor (Midfloor)	\$5870.56
Materials subtotal	\$8347.28
Hardware allowance	\$293.53
Freight surcharge	\$259.22

Indicative range (excl. GST)

\$8,750 – \$9,250

This is an indicative estimate based on information provided and is not a quotation. Actual pricing is subject to final measurements, product availability, and market conditions. The range above reflects an estimate uncertainty band of 5%.

Unit 1 Cladding CLADDING

ELEVATIONS

Area	Orientation	Width (m)	Height (m)	Area (m²)	Cladding
North Elev 1	Vertical	3.20	2.40	7.68	LB Vertical Cladding (Cladding)
Gable	Vertical	4.30	0.60	2.58	LB Vertical Cladding (Cladding)

ORDER SUMMARY

Item	Description	Qty	Unit Price	Line Total
Cutlist output	LB Vertical Cladding (Cladding)	138.60 lm	\$17.26	\$2392.24
Ext Corner	Box Corner (Cladding)	5.50 lm	\$6.75	\$37.12
Scribers	Scriber (Cladding)	8.25 lm	\$5.74	\$47.36

PART TOTAL \$2476.72

Unit 1 Midfloor MIDFLOOR

ORDER SUMMARY

Item	Description	Qty	Unit Price	Line Total
Bathroom	LIB240.88s (I-Joist)	44.00 lm	\$22.50	\$990.00
Remaining Floor	LIB240.88s (I-Joist)	129.25 lm	\$22.50	\$2908.12
Boundary joists	240x45 LVL8 (LVL)	74.25 lm	\$23.75	\$1763.44
Stair void trimmers	240x45 LVL8 (LVL)	8.80 lm	\$23.75	\$209.00

PART TOTAL \$5870.56

LB Vertical Cladding

Unit 1 Cladding

Pattern	Stock Length	Qty off	Cuts	Cut Waste	Leftover
Pattern 1	4200mm	20	3	9mm	444mm
Pattern 2	4200mm	10	1	3mm	1750mm

Pattern 1 — 4.2m stock, 20 off

ID	Length	Mark	Qty
A	2400 + 50mm	North Elev 1	1
B	600 + 50mm	Gable	2
—	444mm	Waste	1



Pattern 2 — 4.2m stock, 10 off

ID	Length	Mark	Qty
A	2400 + 50mm	North Elev 1	1
—	1750mm	Waste	1



STICKS	STOCK (LIN. M)	CUT LENGTH	WASTE
30	126.0	99.5m	20.9%